



NOTES:

1. ALL TREES ARE TO BE NURSERY GROWN AND LOCALLY ADAPTED, BALL AND BURLAP (B&B) PREFERRED.
2. REMOVE ALL TREATED OR PLASTIC-COATED BURLAP, STRAPPING, TWINE, OR WIRE FROM THE ROOT BALL.
3. FOR CONTAINER-GROWN TREES, CAREFULLY REMOVE THE PLANT FROM THE CONTAINER AND CUT ANY MATTED OR CIRCLING ROOTS.
4. TREE WRAP IS OPTIONAL AND MUST BE REMOVED AFTER THE FIRST GROWING SEASON.
5. WATER TREE AFTER PLANTING. FOR MULCH, USE PINE NEEDLES OR SEASONED WOOD MULCH, NO MORE THAN 3 TO 4 INCHES DEEP.
6. STAKING IS NOT REQUIRED. IF STAKING TREES, USE FLEXIBLE 3/4" WOVEN TIE AND ALLOW SLACK FOR TREE TO MOVE IN WIND. REMOVE ALL STAKES AND TIES AFTER FIRST YEAR OF GROWTH.

CITY OF GREENSBORO

STANDARD TREE PLANTING DETAIL